



Office of University Building Official

4400 University Drive, MS 1E4; Fairfax, VA 22030

Telephone: (703) 993-6070

Fire Alarm Systems Inspection Guide

- *Location and installation of devices (control/annunciator panels, smoke detectors, audible/visible devices, pull stations, sprinkler flow and tamper devices, voice communications, etc.).
- *Operational test of fire alarm system, including interconnection with other building systems such as fire suppression, electrical/mechanical, elevator, smoke exhaust systems, etc. Also, see certification checklist for documentation required.
- *Operational test of system using secondary power supply.
- *Fire alarm interconnection with monitoring company.
- Area of rescue assistance communication and ventilation systems.
- Label, red color and lockout means on FACP circuit breakers.
- Test plan documentation has been prepared in accordance with NFPA 72.

*[NFPA 72 record of completion form](#) required, prior to demonstration of system to OUBO.
For additional information go to [NFPA Codes and Standards](#) free access.